

5.取付管(垂直)推進工(鋼管250呼び径100mm)

路 線 番 号 (家屋名)	ます内径 深さ (m)	本管径 (mm)	土被り			取付管延長 (水平) (m)	推進延長 (垂直) (m)	自在曲管 $\phi 100 \times 75^\circ$	特殊支管 $\phi 100$	硬質塩化ビニル 管 $\phi 100 \times L 800\text{mm}$ (本)	接着受け 口カラー $\phi 100$	中込 スペー サー	鋼製鞘管 $250A \times L 500\text{mm}$ (本)	発生土 処分工 (m^3)
			上流(m)	下流(m)	平均(m)									
	(a)		(b)	(c)	(d) $(b+c)/2$	(e) オフセット+1.0m	(f) $d-a-e \times 0.01$	個	個	(g) $d/0.8$	個	個	(h) $d/0.5$	(m^3)
1181-1	$\phi 200$	200	3.78	3.87	3.83	3.00	2.40	1	1	5	4	4	8	0.0562 m^3/m
	H=1.40m													0.215
合 計							2.40	1	1	5	4	4	8	0.215