

5.取付管(垂直)推進工(鋼管250呼び径150mm)

路 線 番 号 (家屋名)	ます内径 深さ (m)	本管径 (mm)	土被り			取付管延長 (水平) (m)	推進延長 (垂直) (m)	自在曲管 $\phi 100 \times 75^\circ$	特殊支管 $\phi 100$	硬質塩化ビニル 管 $\phi 150 \times L 800\text{mm}$ (本)	接着受け 口カラー $\phi 100$	中込 スペー サー	鋼製鞘管 $250A \times L 500\text{mm}$ (本)	発生土 処分工
			上流(m)	下流(m)	平均(m)									
	(a)		(b)	(c)	(d) (b+c)/2	(e) オフセット+1.0m	(f) d-a-e $\times 0.01$	個	個	(g) d/0.8	個	個	(h) d/0.5	(m3)
123	$\phi 200$	200	2.91	3.07	2.99	1.60	1.57	1	1	4	3	3	6	0.0562m3/m
	H=1.40m													0.168
123	$\phi 200$	200	2.91	3.07	2.99	1.60	1.57	1	1	4	3	3	6	0.0562m3/m
	H=1.40m													0.168
123	$\phi 200$	200	2.91	3.07	2.99	4.00	2.15	1	1	4	3	3	6	0.0562m3/m
	H=0.80m													0.168
122-3	$\phi 200$	200	2.78	2.81	2.80	4.00	1.96	1	1	4	3	3	6	0.0562m3/m
	H=0.80m													0.157
122-3	$\phi 200$	200	2.78	2.81	2.80	4.00	1.96	1	1	4	3	3	6	0.0562m3/m
	H=0.80m													0.157
合 計							9.21	5	5	20	15	15	30	0.818